KADUR DIVISION

Dated 28th January 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kadur Division, up to 15th February 1930, till 2 P.M., for constructing the Maternity and Hospital for women at Chikmagalur as an approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions can be seen at the Executive Engineer's Office at Chikmagalur between the hours of 11 A.M. and 3 P.M., on working days.

3. Tenders must be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees five hundred only in Mysore Government Promissory Notes at par value, and be superscribed "Tender for constructing the Maternity and Hospital for women at Chikmagalur in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office for information. No enquiries regarding acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates either below the estimated rates or those of lowest tenders will not be accepted.

10. Rates should be quoted for each item.

11. In all matters of dispute regarding the quality of work and rates, the decision of Chief Engineer is final and legally binding.

Abstract estimate for constructing the Maternity and Hospital for women at Chikmagalur

No.	Items of work	Unit	Quantity	Rate	
				In figures	In words
				Rs.	Rs.
1	Earthwork excavation for foundation and filling in basement.	C.yd.	299		
2	Stone jelly concrete in chunam mortar	c.ft.	2,129		
3	Burnt stone in chunam mortar	„	8,507		
4	Burnt brick do	„	9,721		
5	Burnt stone slabs 6" thick dressed	s.ft.	1,727		
6	Teakwood doors with double shutters 3 glazed and 2 4 panelled with bolts, etc., complete.	„	515		
7	Teakwood windows with glazed shutters and bars, etc., complete.	„	216		
8	Crittal windows including fixing, etc., complete	„	84		
9	Reinforced concrete ventilators as per design.	„	28		
10	T. W. Shelves with glazed shutter and padlock, etc complete.	„	176		
11	Teakwood wrought and put up including woodoiling.	C.ft.	137·09		
12	Cut stone pillars with base and capital 8' height.	No.	12		
13	Do do 6½' ...	„	6		
14	Rolled steel joists (B. S. B.) including hoisting.	C.wt.	186·6		
15	Plastering with chunam mortar with corners rounded off.	Sqr.	153·53		

No.	Items of work	Unit	Quantity	Rate	
				In figures	In words
16	White washing two coats	Sqr.	153·83		
17	Jack arch terrace including plastering ...	,,	28·42		
18	Roofing with 1st class Mangalore tiles on teak reepers.	,,	23·54		
19	Ridging 1st class Mangalore tiles set in mortar and cement pointed.	R.ft.	115		
20	Burnt brick in mortar parapet wall 2½′ high, 1·1/8′ thick including plastering and white washing and coping.	,,	351		
21	Burnt brick in mortar cornice (1′) including plastering and white washing.	,,	351		
22	Flooring with 1st class Mangalore tiles on 3″ concrete and cement pointed.	Sqr.	32·96		
23	Providing and fixing teakwood ornamental eave boards 9″ x 1″ including chocolate painting.	R.ft.	151		
24	Zinc white painting 2 coats	Sqr.	18·20		
25	Cement pointing after scraping joints ...	,,	12·45		
26	Ornamental teakwood large board for darmar including chocolate painting.	L. S.	Rs.		
27	Providing 5′ zinc sheets for valleys ...	R.ft.	56		
28	Do water connection to bath and water closet.	L. S.	Rs.		
29	Do sinks do do ...	No.	6		
30	Do mortar band including cement plastering.	R.ft.	165		
31	Cutting grooves in cill slabs for door posts ...	No.	40		
32	Providing zinc sheet down pipes 4″ dia. ...	R.ft.	150		
33	U. shaped drain alround the building with brick in surki mortar and cement plastered.	L. S.	Rs.		
34	Levelling ground, forming approach road with culvert, etc.	L. S.	Rs.		
35	Boxing girders with cement concrete ...	C.ft.	94		

Abstract Notification.

The attention of the public is invited to the notice calling for tenders for improving Rayakalve of Madag tank published in pages 121 and 123 of Part VI of the *Mysore Gazette*, dated 30th January 1930. The last day for receiving tenders is 18th February 1930 till 3 P.M.

Abstract Notification dated 16th January 1930.

The attention of the public is invited to the notice calling for tenders for constructing quarters for the Executive Engineer at Chikmagalur on pages 96 to 98, of Part VI, of the *Mysore Gazette*, dated 23rd January 1930.

The last date for receiving tenders is 8th February 1930 at 2 P.M.

L. A. H. WINCKLER,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification.

The attention of the public is hereby invited to the advertisement page No. 124 of the *Mysore Gazette* of dated 30th January 1930, calling for tenders for the work of Restoring Malakere (Sannakere) R. No. 32 of Davangere Taluk.